

PHIGENICS ANALYTICAL SERVICES LABORATORY
3S701 West Ave, Suite 100, Warrenville, IL 60555
Telephone: 844-850-4087 Fax: 630-717-8528 Website: www.phigenics.com

A CDC ELITE Certified Laboratory

Facility Tested: Test Site #1 Date of Testing: 2021/01/01 Contact Email: ismith@email.com

Validation Criteria:

Potable Water - typically in well managed systems, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10³ CFU/ml. Per the OSHA *Legionella* Technical Manual, the viable *Legionella* concentration should be less than 10 CFU/ml unless the water system serves immunocompromised or higher risk users which require a more stringent level of *Legionella* control (less than 1 CFU/ml).

Utility Water (such as cooling water) - typically in well managed systems, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10⁴ CFU/ml. For closed recirculating utility water, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10² CFU/ml. Per the OSHA *Legionella* Technical Manual, the viable *Legionella* concentration should be less than 10 CFU/ml. - The facility Water Management Team should review all options for Validation Criteria and choose its specific criteria based on the specific systems and users.

Phigenics Validation Test (PVT) Report Summary

Method Used: TimeZero Method

Legionella Caution		Indicates Legionella was detected.				
THAB Caution		Indicates total heterotrophic bacteria count exceeds the validation criteria (10 ³ for potable, 10 ⁴ for utility, 10 ³ for closed recirculating utility).				
NO Concern	No Shading	Indicates results are better than the validation criteria.				
	ND	Indicates Legionella was not detected.				

PASL Number	Date Inoculated	Date Analyzed	Collector	Location Identification		tegory Detail	Total Bacteria	Lpn S1 CFU	Lpn S2-14 /mL	Legionella Spp
10000	2021/01/01	2021/01/03	J. Smith	Sink #1 Hot	Potable		10 ³	70	ND	ND
10001	2021/01/01	2021/01/03	J. Smith	Sink #2 Cold	Potable		10 ⁵	ND	ND	ND
10002	2021/01/01	2021/01/03	J. Smith	Sink #3 Hot	Potable		10 ²	ND	ND	ND
10003	2021/01/01	2021/01/03	J. Smith	Sink #4 Cold	Potable		<100	ND	ND	ND
10004	2021/01/01	2021/01/03	J. Smith	Shower #1 Hot	Potable		10 ³	30	ND	ND
10005	2021/01/01	2021/01/03	J. Smith	Shower #2 Cold	Potable		10 ²	ND	ND	ND
10006	2021/01/01	2021/01/03	J. Smith	Shower #3 Hot	Potable		10 ⁴	ND	ND	ND
10007	2021/01/01	2021/01/03	J. Smith	Shower #4 Cold	Potable		<100	ND	ND	ND
10008	2021/01/01	2021/01/03	J. Smith	Ice Machine #1	Potable		<100	ND	ND	ND
10009	2021/01/01	2021/01/03	J. Smith	Ice Machine #2	Potable		<100	ND	ND	ND
10010	2021/01/01	2021/01/03	J. Smith	Drinking Fountain #1	Potable		<100	ND	ND	ND
10011	2021/01/01	2021/01/03	J. Smith	Drinking Fountain #2	Potable		10 ²	20	ND	ND
10012	2021/01/01	2021/01/03	J. Smith	Misting System	Potable		10 ⁶	ND	ND	ND
10013	2021/01/01	2021/01/03	J. Smith	Cooling Tower	Utility		10 ⁴	50	ND	ND
10014	2021/01/01	2021/01/03	J. Smith	Closed Loop	Utility		10 ⁴	ND	ND	ND

Disclaimer: Results from the PVT, or from any other analytical protocol for that matter, do not necessarily provide enough evidence to ensure that hazards from pathogenic microorganisms have been eliminated or controlled nor that risk of harm from such hazards has been reduced. Results from the PVT should only be interpreted within the context of properly designed and implemented water management plans. No guarantee regarding results is expressed or implied. THE PVT AND THE RESULTS IT PRODUCES ARE PROVIDED ON AN "AS IS" BASIS. YOU ASSUME TOTAL RESPONSIBILITY AND RISK FOR YOUR USE OF THE PVT AND PHIGENICS IS NEITHER RESPONSIBLE NOR LIABLE FOR ANY DAMAGES ARISING OUT OF YOUR USE OF THE PVT.